



WALL ANGLE 26° UNREINFORCED

NOTES:

1. Maximum allowable height (H) = 3'-8", (h) = 8" increment max.
2. Erect wall in 8" increments and backfill after each stage.
3. Design based on equivalent soil fluid weight = 30 pcf and block weight = 130 pcf.
4. For taller walls or conditions with surcharge consult geogrid reinforcement section.(Dwg's 5-S2 thru 7-S2)
5. For conditions with water runoff, positive discharge drain pipe must be provided.
6. For taller applications: decrease increment (h) to 4", or use geogrid reinforcement per Tables on Dwg's 5, 6 & 7.

© 2001 Synthesis International Inc. - World Rights Reserved

PYRAMID SECTION		
TERRASTOP™ SYSTEM 2		
RAPID BUILDING SYSTEMS P.O. Box 3335 Reston, VA 20195 - USA		
SCALE:	NONE	PROJECT: 99601
DRAWN:	rp	DATE: 6-01
DESIGN:	JP	DRAWING: 3-S2