



WALL ANGLE 11° UNREINFORCED

NOTES:

1. Maximum allowable height (H) = 3'-0", (h) = 1'-4" increment max.
2. Erect wall in 8" increments and backfill after each stage.
3. Design based on equivalent soil fluid weight = 30 pcf and block weight = 130 pcf.
4. For taller walls or conditions with surcharge consult geogrid reinforcement section.(Dwg's 5-S2 thru 7-S2)
5. For conditions with runoff, positive discharge drain pipe must be provided.

© 2001 Synthesis International Inc. - World Rights Reserved

TERRACE SECTION

TERRASTOP™ SYSTEM 2

RAPID BUILDING SYSTEMS P.O. Box 3335 Reston, VA 20195 - USA

SCALE: NONE	PROJECT: 99601	DRAWING:
DRAWN: rp	DESIGN: JP	DATE: 6-01
		2-S2